

GENERAL NOTES

- A. VERIFY AND CONFIRM ALL DIMENSIONS AND CONDITIONS. NOTIFY A/E OF ANY DISCREPANCIES PRIOR TO START OF WORK.
- B. SEE PANEL ELEVATIONS FOR PANEL THICKNESSES.
- C. PATCH AND REPAIR EXISTING WORK DAMAGED DURING CONSTRUCTION TO NEW CONDITION.
- D. VERIFY AND CONFIRM EQUIPMENT LAYOUT WITH OWNER PRIOR TO START OF WORK.
- E. FIREWALLS SHOWN PROVIDED PER OWNER'S REQUIREMENTS TO PROVIDE PROTECTION FOR EQUIPMENT AND ARE NOT REQUIRED BY BUILDING CODE.

KEYNOTES

- 1. COLUMN, SEE STRUCTURAL
- 2. NOT USED
- 3. EXISTING STOREFRONT ENTRY
- 4. PROVIDE (1) LAYER 3/8" GYP BOTH SIDES OVER EXISTING WALL, TO ACHIEVE 2-HOUR FIRE RATING, EXTEND FULL HEIGHT W/(2) LAYERS BOTH SIDES.
- 5. SAWCUT NEW OPENING FOR H.M. DOOR
- 6. ENLARGE EXISTING (2) 3'x7" TO (2) 3'x8" (NEW DOORS).
- 7. NEW WOVEN WIRE MESH AROUND EXISTING PIPES, TO BE REMOVABLE
- 8. HM DOOR, SEE ELEVATIONS FOR MORE INFO.
- 9. DOWNSPOUT & SCUPPER, SEE ROOF PLAN FOR ADDITIONAL INFORMATION.
- 10. NOT USED.
- 11. REMOVE EXISTING WINDOW, INFILL WALL, SEE 1/A8.3
- 12. NOT USED
- 13. EXTEND WALL FULL HEIGHT, TO UNDERSIDE OF ROOF STRUCTURE. ADD (1) NEW LAYER OF GYP BD @ RM 107A SIDE - ADD INSULATION ABOVE EXISTING WALL
- 14. NOT USED
- 15. STOREFRONT W/SPANDREL GLAZING, RECESSED INTO PANEL
- 16. INFILL EXISTING WALL VENT HOLES W/ 2-HR CONSTRUCTION & SAFING
- 17. EXTEND BLOCK MINIMUM 1'-0" BEYOND OPENING
- 18. RELOCATE EXIST. FIRE EXTINGUISHER AS SHOWN
- 19. SEE SHEET "S2.1" FOR WALL BRACING, ALL FINISHES TO BE RETURNED TO NEW CONDITION
- 20. PROVIDE FIREMAN'S LOCK BOX CLOSE TO FRONT ENTRY. COORD' FINAL LOCATION w/OWNER'S REP.
- 21. REMOVE EXIST. FLOORING, ADD NEW V.C.T.
- 22. VCT FLOORING PATH THRU CARPETED ROOM, REPAIR BOTH AS REQUIRED BY NEW CONSTRUCTION
- 23. USG THERMAFIBER 3" SAFB. BATTS @ INTERIOR WALLS OF ROOM 104
- 24. 8" MECHANICAL CURB, SEE DETAIL 2/A8.1. COORD' LOCATION w/MEP.
- 25. -
- 26. NEW SHELVING (SEISMIC ZONE 4)
- 27. EXIST 2x6 PLATFORM TO BE REMOVED
- 28. NEW ENCLOSURE @ ENTRY
- 29. NEW WOVEN WIRE MESH LINK FENCE UP 10'-0" w/5' x 8' SLIDING LOCKABLE GATE, CORE DRILL & GROUT VERTICAL SUPPORTS. COORD' LOCATION w/OWNER'S REP. TO PROTECT UNDERSLAB UTILITIES
- 30. EXISTING ROOF HATCH TO BE ABANDONED
- 31. NEW ROOF HATCH & LADDER
- 32. ADD (2) LAYERS 3/8" TYPE 'X' GYP BD ON 3/8" HAT CHANNELS @ 24"oc, ON 4" 20 GA JOISTS @ 24"oc, BETWEEN ROOF TRUSSES.
- 33. REMOVE ALL FURRING IN EXIST. AREA. CLEAN AND PAINT WALLS.
- 34. FINAL DOOR LOCATIONS TO BE COORD' w/OWNER'S EQUIP. LAYOUT APPROX. LOCATIONS OF UNDERSLAB FIBER OPTIC CONDUITS
- 35. -
- 36. PROVIDE PENETRATION @ EXIST. BLDG FOR NEW EXHAUST VENT, SEE A3.2 FOR MORE INFO.
- 37. DOORS INTO ELECTRICAL CONTROL PANEL ROOM SHALL BE MARKED w/A PLAINLY VISIBLE & LEGIBLE SIGN STATING, "ELECTRICAL ROOM."

LEGEND

- NEW FURRED CONCRETE WALL (W/ INSULATION) SEE DETAIL 11/A8.1. ALIGN FACE OF STUD W/ FACE OF COLUMN.
- NEW FURRING ON EXISTING CONCRETE WALL. ALIGN FACE OF STUD W/ FACE OF COLUMN.
- NEW FULL HEIGHT WALL w/INSULATION
- NEW WALL
- NEW FULL HEIGHT 2 HR WALL - SEE DETAIL 10/A8.2
- NEW FULL HEIGHT 1 HR WALL - SEE DETAIL 12/A8.1
- EXISTING WALL
- EXISTING WALL TO BE REMOVED
- D.S. □ DOWNSPOUT
- EXISTING SOFFIT LIGHT
- FE FIRE EXTINGUISHER

EXIST. F.E. LEGEND

- HALON 1211 2-A-40-B-C 13 LB, SERVICED 6/02
- ABC DRYCHEM, 2-A-40-B-C 13 LB, SERVICED 6/02
- OUTSIDE BLDG. ON FUEL TANK, ABC DRYCHEM, 20-A-120-B-C 20 LB, SERVICED 6/02

GROUP MACKENZIE

Architecture
Interior Design
Land Use Planning

Civil Engineering
Structural Engineering
Transportation Planning

Portland, OR 97201-0039
Tel: 503.224.9560 / 360.695.7879
Fax: 503.228.2885

Client



Project
BROADBAND FACILITY EXPANSION PHASE 2 AND 3

TROUTDALE, OREGON

© GROUP MACKENZIE 2002
ALL RIGHTS RESERVED
THESE DRAWINGS ARE THE PROPERTY OF GROUP MACKENZIE AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER, WITHOUT PRIOR WRITTEN PERMISSION


REVISIONS:

REVISION	LAST REVISION THIS SHEET	REVISION CLOSING DATE	EDITION
A	8	07/30/2002	
B	17	08/12/2002	
C	20	09/13/2002	

SHEET TITLE:
FLOOR PLAN

FIRST ISSUED: 6/18/02
LAST ISSUED: 09/13/02
DRAWN BY: ERA, RTK
CHECKED BY: DRW
SHEET:

A2.1
JOB NO. 990276.01



FLOOR PLAN
1/8"=1'-0"

INCLUDING REVISION C
ISSUED FOR BID 7/3/02